



May 25th, 2026

TO: Sawgrass Homeowners

SUBJECT: Sawgrass Pump Station - Fabricate and Install- 3 Pipes
& 3 Flap Gates

Workscope:

- Fabricate (2) New 42" Stainless Steel Flap gates with ½" Gate,
3/8 members & 1/4" body
- Fabricate (1) New 24" Stainless Steel Flap gates with ½" Gate,
3/8 members & 1/4" body
- Fabricate (2) 20 LF of 1/4" stainless 42" pipes with ½" Flanges
- Fabricate (1) 20 LF of 1/4" stainless 24" pipe with ½ flanges
- Fabricate (2) 30 LF of New 3/8" Mild Steel 42" pipes with 5/8
Flanges (Epoxy coated) Inside and Out
- Fabricate (1) 35 LF of New 3/8" Mild Steel 24" pipes with 5/8
Flanges (Epoxy coated) Inside and Out
- Transport & Deliver to Job site
- Pull (2) Remaining Pumps
- Demo (2) 42" Existing Pipes & Gates
- Demo (1) 24" Existing Pipe and Gate
- Demo Conduit and Concrete
- Demo Concrete cut off wall
- Install New Fabricated Pipes and Gates
- Form and Pour new cut off wall



- Install all (3) Pumps
- Clean & Epoxy discharge support Ibeam
- Install hanging support cables for 42" pumps
- Reseal Embankment to pipes under pump house
- Re-Sod Disturbed Areas
- Place recycled concrete on embankment
- Fill dirt as needed
- The objective of this project is to provide and replace (2) 42" pipes and (1) 24" pipe in a timely manner to avoid high tide. As well as capitalizing on the removal and install of the first pump being repaired. At this time we will be utilizing overtime amongst our team to expedite this project.
- Job will be left in broom clean condition

Total price: \$448,440.00

Please call if you have any questions.

Respectfully submitted,

A handwritten signature in blue ink that reads 'Tim Kuhn'.

Tim Kuhn, Owner