B & B BUILDING SYSTEMS

September 30, 2025

TO: Sawgrass Homeowners

ATT: Mr. Paul Rushton

SUBJECT: Budget proposal for one of your 42" pumps.

We will furnish the labor, materials, and equipment to pull one of your 42" pumps and transport it to our shop in Fort Pierce where we will disassemble it and fabricate a new propeller. The propeller OD will be machined to created a tight fit within the existing propeller shroud. It was noted that there is a gantry crane system in the pump house to remove the gearbox. We are assuming that we can use this crane to remove the gearbox.

We will also replace the bottom seals at this time and check the bottom bushing for wear and proper tolerances.

The pump will be reassembled, pressure cleaned, and painted with black two part epoxy paint. We will transport the pump to your location and install it.

Budget proposal price: $39,750.00

Respectfully submitted,

Tom McFrederick

225 Boyd Road • Fort Pierce, FL 34945 • 772-466-8888